

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-22805-00-00
Spot: S2SWSW Sec/Twnshp/Rge: 18-34S-11E
166 feet from S Section Line, 660 feet from W Section Line
Lease Name: CASEMENT-GRAHAM Well #: 2-A
County: CHAUTAUQUA Total Vertical Depth: 1408 feet

Operator License No.: 33157
Op Name: R. D. ENERGY, INC.
Address: 905 N MONTGOMERY
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40		
PROD	4.5	1408		N.A

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2008 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: RODNEY DICKENS Company: _____ Phone: (620) 725-3065

Proposed Plugging Method: RAN 1" TO 1350' GEL HOLE, SPOTTED 50' CEMENT PLUG. PULLED 1" UP TO 900' SPOTTED 50' CEMENT PLUG. PULLED 1" UP TO 350' CEMENTED TO SURFACE WITH 35 SKS CEMENT. PULLED 1" OUT. TOPPED OFF WELL.

45.76

Plugging Proposal Received By: LARRY MARCHANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2008 5:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to TD gelled hole and spotted 50' plug. Pulled 1" up to 900' and spotted 50' plug. Pulled 1" up to 350' and circulated cement to surface. Pulled 1" out and topped well off. A total of 45 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1358	1367		

RECEIVED
KCC DISTRICT #3

APR 29 2009

CHANUTE, KS

DAS

INVOICED

DATE 5-13-09

INV. NO. 2009061554

KANSAS CORPORATION COMMISSION

MAY 04 2009


RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

PKT