

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-25801-00-00  
Spot: SWSWNESE Sec/Twnshp/Rge: 18-34S-11E  
1590 feet from S Section Line, 1300 feet from E Section Line  
Lease Name: CASEMENT-GRAHAM Well #: 6A  
County: CHAUTAUQUA Total Vertical Depth: 1429 feet

Operator License No.: 33157  
Op Name: R. D. ENERGY, INC.  
Address: 905 N MONTGOMERY  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40		
PROD	4.5	1440		N/A

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/04/2008 8:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: RODNEY DICKENS Company: \_\_\_\_\_ Phone: (620) 725-3065

Proposed Plugging Method: RAN 1" TO 1350' GEL HOLE, SPOTTED 50' CEMENT PLUG. PULLED 1" UP TO 900' SPOTTED 50' CEMENT PLUG. PULLED 1" UP TO 350' CEMENTED TO SURFACE WITH 35 SKS CEMENT. PULLED 1" OUT, TOPPED OFF WELL.

46.44

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/04/2008 5:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1350' gelled hole and spotted 50' plug. Pulled 1" up to 900' and spotted another 50' plug. Pulled 1" up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 45 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1386	1394		

RECEIVED  
KCC DISTRICT #3

APR 29 2009 DAS

CHANUTE, KS

INVOICED

DATE 5-13-09

INV. NO. 2009061554

KANSAS CORPORATION COMMISSION

MAY 04 2009

RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)