

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-25994-00-01  
Spot: SWNESE Sec/Twnshp/Rge: 18-34S-11E  
1400 feet from S Section Line, 1200 feet from E Section Line  
Lease Name: CASEMENT Well #: 9A  
County: CHAUTAUQUA Total Vertical Depth: 1440 feet

Operator License No.: 33157  
Op Name: R. D. ENERGY, INC.  
Address: 905 N MONTGOMERY  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40		
PROD	4.5	1429		

Well Type: EOB UIC Docket No: E20249.2 Date/Time to Plug: 01/16/2009 8:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' plug at TD, 50' plug at 800' and 350' to surface.

416.80

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 01/16/2009 5:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1400' gelled hole and spotted 50' plug. Pulled 1" up to 800' and spotted another 50' plug. Pulled 1" up to 350' and circulated cement to surface. Pulled 1" and topped off well. A total of 45 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

RECEIVED  
KCC DISTRICT #3

APR 29 2009 DAS

CHANUTE, KS

INVOICED

DATE 5-13-09

INV. NO 2009061554

KANSAS CORPORATION COMMISSION

MAY 04 2009


RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)