

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20366-00-00  
Spot: SE Sec/Twnshp/Rge: 17-28S-31W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: ED SHAY Well #: 1-17  
County: HASKELL Total Vertical Depth: 2780 feet

Operator License No.: 9280  
Op Name: WITHERS, LAWRENCE  
Address: 2298 90TH RD  
COPELAND, KS 67837

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	904		WITH 550 SX CMT
PROD	4.5	2797	0	WITH 475 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/21/2009 11:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: PRESTON WITHERS Company: LAWRENCE WITHERS Phone: (620) 668-5588

Proposed Plugging Method: 1ST PLUG RUN TBG TO 1300' & CIRCULATE CMT TO SURFACE. 2ND PLUG PUMP 200 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS OR UNTIL 300# IS REACHED. CUT OFF CASING & SURFACE PIPE BELOW PLOW DEPTH.

90.35

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/21/2009 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FREE POINTED STUCK TBG @ 1581'. STUCK IN SAND DUE TO A GLORIETTA CASING LEAK. SHOT OFF CASING @ 1580' & TOO. TIH W/ 2 3/8" WORKSTRING. 1ST PLUG WITH 25 SX CMT & 25# HULLS AT 1300'. 2ND PLUG WITH 80 SX CMT & 50# HULLS AT 952'. TOO. W/TBG. TOP OFF 4 1/2" CASING WITH 10 SX CMT. STAYED FULL. PUMP 40 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. PRESSURE TO 200# & HELD.

Perfs:

Top	Bot	Thru	Comments
2765	2775		
2732	2736		

**INVOICED**  
DATE 5-13-09  
INV. NO. 2009061555

KANSAS CORPORATION COMMISSION


**MAY 06 2009**  
**RECEIVED**

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

APR 23 2009

KCC DODGE CITY

Form CC-273