

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-01546-00-01
Spot: NWSESE Sec/Twnshp/Rge: 16-19S-2W
1015 feet from S Section Line, 1091 feet from E Section Line
Lease Name: H P UNRUH Well #: 2
County: MCPHERSON Total Vertical Depth: 3040 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4	2978		130 SX
PKR	4000	570		
PROD	5.5	2976		135 SX
SURF	8.62	156		90 SX

Well Type: ~~SWD~~ FOR UIC Docket No: EOS630.1 Date/Time to Plug: 03/24/2009 10:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: BRYAN HESS Company: HESS OIL CO. Phone: (620) 241-4640

Proposed Plugging Method: SEE BELOW
98.80

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2009 3:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

ATTEMPT TO PULL TUBING AND PACKER. TUBING PULLED APART. PACKER STUCK AT 570' WITH 150' OF TUBING ABOVE. CONNECT ON TO 4" LINER, ESTABLISH RATE PUMPING WATER OF 4 BB'S PER MINUTE AT 400#S. PUMPED 50 SX'S CEMENT WITH 2% CALCIUM FOLLOWED BY ANOTHER 50 SX'S CEMENT WITH COTTON HULLS. PUMP WIPER PLUG DOWN TO TOP OF TUBING, HELD PRESSURE AT 1500#S. PERFORATE AT 280', CIRCULATE CEMENT TO SURFACE WITH 175 SX'SX.

Perfs:

Top	Bot	Thru	Comments
2978	3040		OPEN HOLE
2330	2340	CSG	

INVOICED
DATE 4-27-09
INV. NO. 2009061454

RECEIVED
KANSAS CORPORATION COMMISSION
APR 10 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. CONSOLIDATED #20560. LOG TECH TICKET #5686.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

JK

PK