

6 030726

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-063-21, 031-00-00

CNESENE SEC. 10, T 11 S, R 30(W)

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name VERHOEFF Well # 1

Operator: ABERCROMBIE DRUG INC.

County GOVE 148,85

Name & Address 801 UNION CENTER

Well Total Depth 4580 feet

WICHITA, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67202

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ABERCROMBIE DRUG INC. License Number 5422

Address \_\_\_\_\_

Company to plug at: Hour: PM Day: 18 Month: 4 Year: 19 86

Plugging proposal received from WALLY TOWNS

(company name) ABERCROMBIE (phone) \_\_\_\_\_

were: 8 5/8 261' w/ 170SX. CIRC. HOLE w/ HEAVY MUD MAINTAIN FLUID LEVEL @ SURFACE SPOT PLUGS WITH D.P. BALANCE w/ MUD ORDER 200 SX. 60/40 PPT 68 GEL 3% CC BJT TITAN CMT. CO.

Plugging Proposal Received by Carl Goodnow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:30 PM Day: 18 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT SPOT D.P. @ 2425' DISPLACE 2.5 SX. CMT. MIX. LAYDOWN D.P. TO 1500' DISPLACE 100 SX. CMT MIX. + 1 SX. HULLS LAYDOWN D.P. TO 300' DISPLACE 40 SX. CMT. MIX. LAYDOWN D.P. ADJUST MUD LEVEL @ 40' ± LOAD HOLE TO BASE OF CELLAR w/ 10 SX. CMT. MIX. DISPLACE 15 SX. CMT. MIX. IN RATHOLE 10 SX. CMT. MIX. IN MOUSEHOLE. PLUG COMPLETE

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

MAY 16 1986

16-86  
5-15-86

DATE MAY 16 1986

Signed Carl Goodnow  
(TECHNICIAN)

INV. NO. 13841