

5-27

15-063-20536-00-00

4-031820

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-20,536
150' SW of C.
NE NE /4 SEC. 15, 11 S, 30 W
4545 feet from S section line
735 feet from E section line

Operator license# 6568 Lease Baalman well # 2

Operator: Kaiser-Francis Oil Company County Gove

Address: P.O. Box 21468 Well total depth 4558 feet
Tulsa, Oklahoma 74121-1468 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 409 feet

14813

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 27 Month: May Year: 93

Plugging proposal received from: Gordon and District #4 Dennis Hamel

Company: Kaiser-Francis Oil Company Phone:

Were: Order 350 sx. 60/40 pozmix - 10% gel. - 400# hulls.
Shots @ 2390' and 1490'.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:10 P.M., Day: 27, Month: May, Year: 93

Actual plugging report: 8 5/8" set @ 409' w/265 sx. cwc. 5 1/2" set
@ 4292' w/200 sx. Perf. 4016' - 4166'. Squeezed 8 5/8" w/50 sx.
cement blend to Max. P.S.I. 300#. Close in P.S.I. 300#.
Squeezed 5 1/2" w/310 sx. cement blend w/500# hulls mixed in to
Max. P.S.I. 400#. Close in P.S.I. 400#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anyh. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation:

I did [X] / did not [] observe the plugging.

INVOICED

DATE 6-17-93

INV. NO. 37942

5-27

Carl Goodrow
 (agent)
Wichita, Kansas

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1993