

4-031739

8-24

15-063-20308-00-00

217  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-063-20,308-00-00

C SE SE /4 SEC. 33, 11 S, 30 W  
660 feet from S section line  
660 feet from E section line

Operator license# 5701 Lease Jensen well # 1

Operator: National Oil Company County Gove 147.71

Address: P.O. Box 399 Well total depth 4545 feet  
Garden City, Kansas 67648 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 230 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Halliburton License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 24 Month: August Year: 92

Plugging proposal received from: Dean Ives

Company: National Oil Company Phone:     

Were: Order 350 sx. 60/40 pozmix - 10% gel. - 500# hulls.  
Hole open by wireline.  
Shots @ 2300' and 1150'.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 3:15P.M., Day: 24, Month: August, Year: 92

Actual plugging report: 8 5/8" set @ 230' w/200 sx. cwc. 5 1/2" set @  
4544' w/200 sx. P.B.T.D. 4495'. Perf. 4490' - 4493'. Ran tubing to  
1980'. Displace 100 sx. cement blend to 1170'. Lay down tubing to  
1170'. Circulate cement slurry to surface. Lay down tubing. Squeeze  
5 1/2" with total of 165 sx. cement blend w/450# hulls mixed in to  
Max. P.S.I. 800#. Close in P.S.I. 300#. Squeeze 8 5/8" w/135 sx. cement  
blend w/50# hulls mixed in to Max. P.S.I. 800#. Close in P.S.I. 300#.  
Plug complete.

Remarks:  
Condition of casing(in hole): GOOD X BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation:      GL     

I did X / did not [      ] observe the plugging.

Carl Goodrow

HD

INVOICED  
DATE 10-8-92  
INV. NO. 36395

(agent)

RECEIVED  
STATE CORPORATION COMMISSION  
9-16-1992  
SEP 16 1992  
CONSERVATION DIVISION  
Wichita, Kansas