

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1984

6 070153

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-063-20,764-00-00

C-SW-5E, SEC. 33, T11 S, R30

660 feet from N¹⁰ section line

1980 feet from W¹⁰ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name JENSEN Well # 1

Operator: AMERICAN ENERGIES CORP.

County GOVE

Name & Address 575 FOURTH FIN CTR.

Well Total Depth 4550 147.88 feet

WICHITA, KANS. 67202

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor ABERCROMBIE DRILLING, INC. License Number 5422 TAG # 185

Address 801 UNION CENTER, WICHITA, Mo. 67202

Company to plug at: Hour: 9:00 AM Day: 18th Month: MAY Year: 19 84

Plugging proposal received from WAYNE SHIVELY

(company name) ABERCROMBIE DRILLING INC (phone) 316-263-5785

were: 8 5/8" - 211 FT SP. CUC w/ 200 SK COMMON GEL - CA-CL - BY SAN CMT.

ORDER - 195 SK 50% POZ MIX GEL - CA-CL - 1 SK CEMENT FLAKE AND 8 5/8" PLUG

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

NO ARBUCKLE - (MISS FOR.) ELV. 2889, ANH. 2356, NO CIRCULATION

PROBLEMS.

Plugging Proposal Received by Marion Schmidt (TECHNICIAN) BOK

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:30 AM Day: 18th Month: MAY Year: 19 84

ACTUAL PLUGGING REPORT

ORDERED 195 SK 50% POZ MIX GEL - CA-CL - 1 SK CEMENT - AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

1st Plug @ 2370 FT w/ 25 SK CMT. → 2nd Plug @ 1480 FT w/ 100 SK CMT w/ 1 SK CEMENT FLAKE.

3rd Plug @ 230 FT w/ 50 SK CMT. → 4th Plug SAND BRIDGE FLAKE - PLUG - 40 FT w/ 10 SK CMT.

10 SK IN RAT HOLE - (CIRCULATE) CEMENTED BY SAN CMT.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-30-84

INV. NO. 1733

Signed Marion Schmidt (TECHNICIAN) BOK

5-18 JUN 04 1984