


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Gove County, Sec. 10 Twp. 11 Rge. 30 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
C of NE NE
Lease Owner American Public Energy Co.
Lease Name Verhoff #1 Well No.
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole)



Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/13/77 19
Plugging completed 9/16/77 19
Reason for abandonment of well or producing formation

depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4744
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	332	none
				4 $\frac{1}{2}$	4238	1411

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 4100' and ran 4 sacks cement. Shot pipe at 3815', 3605', 3015', 1995', 1525', 1405', pulled 36 joints. Squeezed with 3 sacks hulls, 70 sacks cement, 19 sacks gel, released plug and displaced with 60 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
9-23-1977
SEP 23 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
R. DARRELL KELSO


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

Subscribed and sworn to before me this 21st day of Sept. 19 77

My commission expires



Margaret Melcher
Notary Public.

DRILLERS LOG

OPERATOR: AMPECO
 744 Campbell Centre
 8350 N. Expressway
 Dallas, Texas 75206

LEASE: Verhoeff No.1
 NE NE Sec. 10-11S-30W
 Gove County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 408 One Twenty Building
 Wichita, Kansas 67202

COMMENCED: 12/18/76

COMPLETED: 1/3/77

RTD 4744'

CASING: 323.67' new 8-5/8" set at 332' with 225 sacks cement

OIL STRING: Ran 4½" casing, set at 4238 with 75 sacks.
 Plug down 12:00 a.m. 1/3/77

0' to 336' 12½" surface hole
 336' to 1471' Shale & shells
 1471' to 2408' Shale
 2408' 2440' Anhydrite
 2440' to 2605' Shale
 2605' to 2775' Shale & Lime
 2775' to 3014' Lime & Shale
 3014' to 3272' Shale & Lime
 3272' to 3984' Lime & Shale
 3984' to 4231' Lime
 4231' to 4338' Lime & Shale
 4338' to 4435' Shale & Lime
 4435' to 4744' Lime
 RTD 4744'

RECEIVED
 STATE CORPORATION COMMISSION
 8-26-1977
 AUG 26 1977

STATE OF KANSAS
 COUNTY OF SEDGWICK

CONSERVATION DIVISION
 Wichita, Kansas

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state that the above and foregoing is an accurate copy of the log of the Verhoeff No. 1 well.

James C. Remsberg
 JAMES C. REMSBERG

Subscribed and sworn to me on January 5, 1977

Mary Lou Taylor
 Mary Lou Taylor, Notary

My commission expires January 17, 1977

