

15-063-20741-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-063-20741-00-00

LEASE NAME Swart

WELL NUMBER 19-1

SPOT LOCATION SW/SW/SW

SEC. 19 TWP. 11 RGE. 30 (E) OR (W)

COUNTY Gove

DATE WELL COMPLETED 3/19/84

PLUGGING COMMENCED 3/20/83

PLUGGING COMPLETED 3/20/84

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR High Summit Oil & Gas, Inc.

ADDRESS 3817 Carson St., Evans, CO 80620

PHONE # (303) 330-7600 OPERATORS LICENSE NO. 9380

CHARACTER OF WELL D&A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? District #6, Hays, Kansas

IS ACC-1 FILED? yes IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION Cherokee DEPTH TO TOP 4512 BOTTOM 4575 T.D. 4644

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Cedar Hills	water	1300	1360	8-5/8	303'	0
Dakota	water					
Lansing	possible oil	4010	4268			
Marmaton	possible oil	4310	4360			
Cherokee	possible oil	4512	4570			

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Hole was full of 96 ppg equalized 20 sack plug of 50/50 POZ 6% gel 3% CaCl cmt @ 2500'. Equalized 100 sack plug of 50/50 POZ 6% gel 3% CaCl [1 sack Flocele cmt @ 1550']. Equalized 40 sack plug of 50/50 POZ 6% gel 3% CaCl cmt @ 350'. Equalized 10 sack plug of 50/50 POZ 6% gel 3% CaCl 0'-40'. Plugged csg. stub with plug. Plugged rat hole with 10 sack plug of cement.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Sun Oil Well Cementing LICENSE No.
ADDRESS Box 169 Great Bend, Kansas 67530

STATE OF Colorado COUNTY OF Weld, SS.

Wendall H. Jamison (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) *Wendall H. Jamison*

(ADDRESS) 3817 Carson, Evans, CO 80620

SUBSCRIBED AND SWORN TO BEFORE ME THIS 29 DAY OF March, 19 84



Julie Ann Gallego
NOTARY PUBLIC

1215 32 St.
Evans, CO 80620

RECEIVED
STATE CORPORATION COMMISSION
4-2-1984
APR 02 1984

FORM CP-4
REVISED 06-83

CONSERVATION DIVISION
Wichita, Kansas