

15-063-20308-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-063-20,308-00-00

LEASE NAME Jensen

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

660 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 33 TWP. 11 RGE. 30 (E) or (W)

COUNTY Gove

LEASE OPERATOR National Oil Co.

ADDRESS P. O. Box 399, Garden City, Ks. 67846

PHONE# (316) 275-2963 OPERATORS LICENSE NO. 5701

Date Well Completed 10-09-76

Character of Well Oil

Plugging Commenced 08/24/92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 08/24/92

The plugging proposal was approved on 08/20/92 (date)

by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filled? yes If not, is well log attached?

Producing Formation Mississippi Depth to Top 4490 Bottom 4544 T.D. 4544

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	230	none
				5 1/2	4544	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated at 1960' & 1150'. Run tubing to 1940', spotted 50 sks. 65/35/10% gel nozmix. Pulled tubing to 1170', circulated cement to top. Mix 90 sks cement with 150# hulls. Pulled tubing, hook to 5 1/2 casing. Pump 10 sks. cement, pressure 800#. Hooked on to Braden head, pumped 135 sks. cement, 150# hulls. Shut in 300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services

License No. RECEIVED STATE CORPORATION COMMISSION 10-15-1992 OCT 15 1992

Address Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: National Oil Co.

STATE OF Ks COUNTY OF Finney, ss.

CONSERVATION DIVISION  
Wichita, Kansas

Dean Jues (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean Jues

(Address) \_\_\_\_\_

NOTARY PUBLIC  
DONNITA L. THODE  
Finney County  
STATE OF KANSAS  
My Appt. Exp. 11/9/94

SUBSCRIBED AND SWORN TO before me this 13th day of October, 1992

Donnita L. Thode  
Notary Public

My Commission Expires: 11/9/94