

15-109-00013-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

T 11S NORTH R 32W


Locate well correctly on above  
Section Plat

Logan

County. Sec. 3 Twp. 11S Rge. 32W (E) (W)

Location as "NE/CNWxSWx" or footage from lines NW SE SW  
Lease Owner Lawrence Supply Co., Inc.  
Lease Name Bertrand Well No. 1  
Office Address Box 448 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 3 19 56  
Application for plugging filed November 30 19 56  
Application for plugging approved December 3 19 56  
Plugging commenced December 18 19 56  
Plugging completed December 22 19 56  
Reason for abandonment of well or producing formation Explored

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4750 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	277'	None
				5-1/2"	4738'	1921'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled the hole with sand from 4750' to 4729' and ran 4 sacks of cement which filled to 4707'. Mudded the hole to 270', set a 10' rock bridge and ran 20 sacks of cement. Mudded the hole to 35', set a 10' rock bridge and ran 10 sacks of cement which filled to base of cellar. Plugging completed.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 26th. day of December 19 56  
Edward E. O'Brien  
Edward E. O'Brien Notary Public.

My commission expires May 20, 1957

PLUGGING  
FILE SEC. 3 T. 11 R. 32W  
BOOK PAGE 121 LINE 13

12-27-1956

CONSERVATION DIVISION  
WICHITA, KANSAS

15-109-00013-00-00

DRILLERS LOG

Bertrand #1  
Commenced R.D.: 2-13-56  
Completed R.D.: 3-8-56  
Total Depth: 4750'  
Casing record: 277' of 8 5/8"  
4788' O.A. 5 1/2"

App. NW SE SW, Sec. 3-115-32W  
Logan County, Kansas  
Elevation: 3046 D.F.  
Initial Prod.: None  
Contractor: Buick Drilling Inc.

STRATA	DEPTH
Surface clay	0 - 40
Sand, gravel and clay	40 - 250
Blue shale	250 - 277
Shale and shells	277 - 1000
Chalk and lime	1000 - 1080
Shale	1080 - 1390
Sand and shale	1390 - 1570
Chalk, shale and shells	1570 - 1785
Sand, shale, anhydrite, and red bed	1785 - 2125
Red bed, shale and anhydrite	2125 - 2720
Red bed, shale and shells	2720 - 3095
Shale and shells	3095 - 3265
Shale, shells and lime	3265 - 3402
Shale, sand and chert	3402 - 3456
Chert	3456 - 3485
Shale, lime and shells	3485 - 3525
Shale and lime	3525 - 3824
Lime	3824 - 3945
Lime and shale	3945 - 4040
Lime	4040 - 4150
Chalky lime	4150 - 4215
Lime	4215 - 4315
Lime and shale	4315 - 4385
Lime	4385 - 4435
Shale and lime	4435 - 4665
Lime	4665 - 4625
Shale and sand	4625 - 4660
Lime	4660 - 4745
Lime and shale	4745 - 4750 T.D.

I hereby certify the above a true and correct drilling log as reflected by the drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.

*H. R. Buick*  
H. R. Buick, President

Signed and sworn to in my presence this 28th day of November, 1956, by H. R. Buick, President of the Buick Drilling Inc.

*Robertas Shegrew*  
Notary Public

My commission expires December 26, 1959.

PLUGGING  
FILE SEC 3 T 11 R 32W  
BOOK PAGE 121 L L 13

RECEIVED  
STATE CORPORATION COMMISSION  
12-7-1956  
DEC 1 - 1956  
CONSERVATION DIVISION  
Wichita, Kansas