

Kansas Corporation Comm.
Wichita State Office Bldg.
130 S. Market, Room 2078
Wichita. KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

NUMBER 109-20607 0000

LEASE NAME Clarence Heyen

WELL NUMBER 1

330 Ft. from S Section Line

1440 Ft. from E Section Line

SEC. 5 TWP. 11S RGE. 32 (E) or (W)

COUNTY Logan

Date Well Completed 12/20/95

Plugging Commenced 5:00PM 12/20/9

Plugging Completed 7:45PM 12/20/9

15-109-20607-00-00

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Wanker Oil

ADDRESS RR#2 Box 14 Wakeeney, Kansas 67672

PHONE# (913) 743-2769 OPERATORS LICENSE NO. 3966

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/19/95 (date)

by Ed Schumacher (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.O. 4700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	259.48	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

1st Plug @ 2600' w/20sks 15sks In Rat Hole Circulated 1st Plug 15 Minutes w/48 Vis Mud

2nd Plug @ 1685' w/100sks 10sks In Mouse Hole Plugs Displaced w/ Mud

3rd Plug @ 310' w/40sks

4th Plug @ 40' w/10sks 195sks Total 60/40Poz 6%Gelw/1/4#FS/sk By Allied Cementing Co 7:45PM 12/20/95

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601-0763

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Wanker Oil

STATE OF KANSAS COUNTY OF TREGO, ss.


Patrick Wanker (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed; the same are true and correct, so help me God.

(Signature) Patrick Wanker

(Address) RR-2-Box 14 - Wakeeney Kansas

SUBSCRIBED AND SWORN TO before me this 11 day of February, 1996

My Commission Expires:



Notary Public