

4-060721

7-23

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-195-22,157-00-00

110' N. of  
SE NW NE /4 SEC. 15, 11 S, 25 W  
4390 feet from S section line  
1650 feet from E section line

Operator license# 3736

Lease: Palkowsky Well # 1-15

Operator: RLT Investments

County: Trego 130.98

Address: HCR-01 - Box 63  
Morland, Kansas 67650

Well total depth 4030 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Mallard J.V. Inc. License# 4958

Address: P.O. Box 1009 - McPherson, Kansas 67460

Company to plug at: Hour: 12:00 A.M. Day: 23 Month: July Year: 1995

Plugging proposal received from: Carol

Company: Mallard J.V. Inc. Phone: 316-241-4640

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 12:00 A.M., Day: 23, Month: July, Year: 1995

Actual plugging report:  
1st. Plug at 2080' with 25 sxs. - Anhydrite 2059' - 2100'.  
2nd. Plug at 1175' with 100 sxs. - Dakota 860' - 1160'.  
3rd. Plug at 260' with 40 sxs. - Surface pipe to 208'.  
4th. Plug at 40' with 10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 30 1995  
08-30-1995  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: Halliburton Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 2460 GL

I did [ ] / did not [ X ] observe the plugging.

[Signature] (agent)  
Form CP-2/3

INVOICED  
DATE 8-31-95  
INV. NO. 43389