

4-050183

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-063-21,470

SE SE SW /4 SEC. 10, 11 S, 31 W  
330 feet from S section line  
2970 feet from E section line

Operator license# 4767

Lease Walz well # 1

Operator: Ritchie Exploration Inc.

County Gove

Address: 125 N. Market Suite 1000  
Wichita, Kansas 67202  
(316)267-4375

Well total depth 4685 feet <sup>152.26</sup>  
Conductor Pipe: \_\_\_ inch @ \_\_\_ feet  
Surface pipe 8 5/8 inch @ 210 feet

Aband. oil well \_\_\_\_, Gas well \_\_\_\_, Input well \_\_\_\_, SWD \_\_\_\_, D & A X

Plugging contractor: White & Ellis License# 5420

Address: \_\_\_\_\_

Company to plug at: Hour: AM Day: 13 Month: December Year: 1993

Plugging proposal received from: Judy

Company: White & Ellis phone: \_\_\_\_\_

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2550 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1700 feet " 100 "

3rd plug @ 260 feet " 40 "

4th plug @ 40 feet " 10 " with 8 5/8" wiper plug

Plugging Proposal Received by: Marvin L. Miller

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 8:30 AM, Day: 13, Month: December, Year: 1993

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 1/4# celloflake or flowcel per sk

Remarks: Elevation: 2998, Anhydrite: 2531-2561 feet, Anhydrite plug: 2550  
Bottom plug (in place): Yes X, Calc \_\_\_\_, No \_\_\_\_, Arbuckle: None

Did NOT penetrate Arbuckle, cemented by Allied Cementing Company

I did  observe the plugging.

*Marvin Miller*  
Marvin L. Miller P. I. Wichita, Kansas  
(agent)

RECEIVED  
STATE CORPORATION COMMISSION  
12-14-1993  
DEC 14 1993  
CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**  
DATE 12-15-93  
INV. NO. 39542  
12-13