

4- 062651

6-4

21
21

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-21,435-00-00

NE NW NW /4 SEC. 12 , 11 S, 31 W
330 feet from S section line
990 feet from E section line

Operator license# 8541

Lease Hazelton well # 3

Operator: Petex, Inc.

County Gove

Address: 1610 E. Sunshine
Springfield, MO 65804
417-887-1225

Well total depth 4630 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 213 feet
w/ 40 sks.

150.47

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: _____

Company to plug at: Hour: 11:15A.M Day: 2 Month: June Year: 92

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone: 417-887-1225

Were: Order 240 sx. cement 60/40 pozmix - 6% gel. & 2 sx. flocele.
Heavy mud between all plugs. Pump cement down drill pipe.

Plugging Proposal Received by: Gilbert G. Scheck
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 6:30P.M., Day: 4, Month: June, Year: 92

Actual plugging report: 25 sx. @ 2527'.
100 sx. @ 1500'.
60 sx. @ 1000'.
40 sx. @ 240'.
15 sx. in Rathole.

Remarks: Plug water well to 300' w/40 sxs. - By Allied.
Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X NO
Plugged through TUBING , CASING X. Elevation: 2950

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1992
6-12-1992
CONSERVATION DIVISION
Wichita, Kansas

I did [X] / did not [] observe the plugging.

Gilbert G. Scheck
(agent)

INVOICED
DATE 6-30-92
INV. NO. 35598