

6-031453

API NUMBER 15-

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NW SW, SEC. 12, T 11 S, R 31 W/E  
2310 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8541

Lease Name Hazelton Well # 2

Operator: Petex Inc.

County Gove 141.37

Name & Address 1111 S. Glenstone Suite 1-10

Well Total Depth 4350 feet

Springfield, Mo. 65804

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Poe Well Service License Number 3152  
Oberlin, Ks.

Company to plug at: Hour: PM Day: 16 Month: Nov Year: 19 90

Plugging proposal received from Earl Evers

(company name) Petex (phone)

were: 8 5/8 set at 200 cwc. 4 1/2 set at 4350 w/250 sks. PBDT 4336. Perf 4277 - 87.

Shot at 2501 - 02. anhy, freepoint 1290. Shot and recovered casing. Order sand and common cement. Pull pipe. Order 250 sks 65/35 poz 10% gel 500 lbs. hulls. B. J. Titan.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5:30 PM Day: 16 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 4220 bail in 4 sks common cement on sand.

Freepoint at 1290. Shot recovered 1290 of 4 1/2 casing. Sq 8 5/8 w/250 sks cement blend w/500 lbs. hulls mixed in to max psi 200 lbs. Close in psi 200 lbs. Plug c complete. The port collar at 2452 would not open for alt 2 completion so well was plugged.

STATE CORPORATION COMMISSION

11-28-1990  
NOV 28 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-90

INV. NO. 30153  
11-16

*hls*

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow