

4-031963

8-18 15-063-21249-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-21,249
100'E. of
NE NW NE /4 SEC. 06 , 11 S , 31 W
4950 feet from S section line
1550 feet from E section line

Operator license# 5086 Lease Miller Trust well # A-1
Operator: Pintail Petroleum, Inc. County Gove
Address: 225 North Market Well total depth 4700 feet ^{152.75}
Suite #300 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 233 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: D S & W Well Service, Inc. License# 6901

Address: Claflin, Kansas

Company to plug at: Hour: P.M. Day: 18 Month: August Year: 94

Plugging proposal received from: Kevin

Company: D S & W Well Service, Inc. Phone: _____

Were: Order 210 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.

RECEIVED
STATE CORPORATION COMMISSION
8-24-1994
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 6:45P.M. , Day: 18 , Month: August , Year: 94

Actual plugging report: 8 5/8" set @ 233' w/150 sxs. 4 1/2" set @ 4294'
w/150 sxs. cwc. Prod. perf. 4196' - 4198'. Port collar @ 2550' w/275 sxs
cwc. Blanked off below CIBP @ 4160' - open perms 4112' - 4121'. Squeezed
8 5/8" with one bbl. To max. P.S.I. 500#. Close in P.S.I. 500#.
Squeezed 4 1/2" w/120 sxs. cement blend w/500# hulls. To Max. P.S.I.
2000#. Close in P.S.I. 2000#.

Remarks: _____
Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging. Carl Goodrow

DATE 9-6-94
INV. NO. 41100

(agent) 170
Form CP-2/3