

4-031964

8-18

15-063-21053-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-21,053

SW SE NW /4 SEC. 05, 11 S, 31 W
2970 feet from S section line
3630 feet from E section line

Operator license# 5086

Lease Jorden A well # 1

Operator: Pintail Petroleum, Inc.

County Gove

Address: 225 North Market
Suite #300
Wichita, Kansas 67202

Well total depth 4680 feet ^{152.10}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 349 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: D S & W Well Service, Inc. License# 6901

Address: Claflin, Kansas

Company to plug at: Hour: P.M. Day: 18 Month: August Year: 94

Plugging proposal received from: Kevin

Company: D S & W Well Service, Inc. Phone: _____

Were: Order 210 sxs. 60/40 pozmix - 10% gel - 500# hulls
Allied Cement Company.
Order 3 sxs. gel.

RECEIVED
STATE CORPORATION COMMISSION
8-24-94
AUG 26 1994
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 4:30P.M., Day: 18, Month: August, Year: 94

Actual plugging report: 8 5/8" set @ 349' w/200 sxs. 4 1/2" set @ 4676'
w/425 sxs. cwc. Prod. perf. 4263' - 4266' - 4549' - 4551'. CIBP @
4590'. Tested 8 5/8" w/ @ sxs. to Max. P.S.I. 300#. Squeezed 4 1/2"
w/50 sxs. cement blend w/200# hulls mixed in, followed with 3 sxs. gel
and 160 sxs. cement blend w/300# hulls mixed in to Max. P.S.I. 700#.
Close in P.S.I. 300#.

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did did not observe the plugging. Carl Goodrow

INVOICED

DATE 9-6-94

WV. NO 4111

(agent)