

4-071049

API number: 15-063-21,146

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE SE /4 SEC. 11, 11 S, 31 W  
2310 feet from S section line  
330 feet from E section line

Operator license# 9860

Lease Lockwood well # 1

Operator: Castle Resources, Inc.

County Gove

Address: 1200 East 27th Street  
Suite C  
Hays, Kansas 67601

Well total depth 4650 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 225 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cementing License#     

Address: P.O. Box 31 - Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 26 Month: May Year: 93

Plugging proposal received from: Terry Williamson

Company: Castle Resources, Inc. Phone: 913-625-5155

Were: 8 5/8" - 225' S.P. cwc. w/145 sx. cement. 4 1/2" casing set  
@ 4498' w/200 sx. cement. D.V. tool @ 2470' w/550 sx. cement. Casing  
good. Proposal - 275 sx. 60/40 pozmix - 10% gel. and 5 sx. hulls.  
Pump in with pump truck.

1) Pump in annulus with cement pressure annulus space.

2) Pump in 4 1/2" casing 15 sx. cement followed w/200 sx. cement plus  
Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 1:00P.M., Day: 26, Month: May, Year: 93

Actual plugging report: Castle Resources Inc. ordered 275 sx. 60/40  
pozmix - 10% gel. - 5 sxs. hulls. Pumped in with pump truck.

1) Pumped 4 sx. cement in 4 1/2" x 8 5/8" annulus. Max. pressure  
500# P.S.I. Shut in 500#. 2) Pumped in 4 1/2" casing w/15 sx. cement  
followed w/256 sx. cement with 2 sx. hulls. 3) Returned for more  
cement. 4) Pumped an additional 12 sx. cement in 4 1/2" casing.  
Max. pressure 600# P.S.I. Shut in 600#.

Remarks: Cemented by Allied - Oakley, Kansas

Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO     

Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X NO     

Plugged through TUBING     , CASING X. Elevation:     

I did not observe the plugging.

INVOICED

DATE 6-14-93

INV. NO. 37897

5-26

RECEIVED  
JUN 9 1993  
STATE CORPORATION COMMISSION  
Wichita, Kansas  
Form CP-2/3  
(agent)