

4-032045

2-7 15-063-21192-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-21,192

NW NW SW /4 SEC. 12, 11 S, 31 W
2310 feet from S section line
4950 feet from E section line

Operator license# 8541

Lease Hazelton well # 1

Operator: Petex, Inc.

County Gove

Address: 1610 E. Sunrise
Springfield, Missouri
65804

Well total depth 4605 feet ^{149.66}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 251 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 7 Month: February Year: 95

Plugging proposal received from: Ron

Company: Allied Cement Company Phone:

Were: Order 160 sxs. 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:00A.M., Day: 7, Month: February, Year: 95

Actual plugging report: 8 5/8" set @ 251' w/150 sxs. cwc. 4 1/2" set @
4600' w/525 sxs. cwc. Prod. perf. 4402' - 4404'. Squeezed 8 5/8" with
15 sxs. cement blend to Max. P.S.I. 350#. Close in P.S.I. 350#.
Squeezed 4 1/2" w/25 sxs. cement blend w/100# hulls mixed in, followed
by 12 sxs. gel, followed by 120 sxs. cement blend w/400# hulls mixed
in to Max. P.S.I. 1000#. Close in P.S.I. 1000#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: GL

I did X did not[] observe the plugging. Carl Goodrow

INVOICED
DATE 2-24-95
INV. NO. 42263

(agent)
Form CP-2/3

RECEIVED
FEB 21 1995
2-21-1995
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS