

6 070547

15-063-21097-00-00

150 R

API NUMBER 15-063-21,097

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C-SE-NW, SEC. 16, T 11 S, R 31 W

3300 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8541

Lease Name Hockersmith # 2

Operator: Petex, Inc

County Cove 152.75

Name & Address Route 2 - Box 553

Well Total Depth 4700 feet

Rogersville, Mo. 65742

Conductor Pipe: Size 0 feet

Larry Childress

Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated Tag # 1828

Plugging Contractor R & C Drilling Co. Inc. License Number 9087

Address P.O. Box 296 Hays, Kans. 67601

Company to plug at: Hour: 1:00 AM Day: 13th Month: March Year: 19 87

Plugging proposal received from John Weiss

(company name) R & C Drilling Company Inc (phone) 417-887-6289

were: 8 5/8" - 220 FT SP. CUC 2 1/4" 5^{SK} 60/40 Pozmix 2% Gel - 3% Ca-Cl, by Allied

Proposal - Order 190 5^{SK} 60/40 Pozmix 6% Gel - 3% Ca-Cl, 1 cello + 8 5/8" Plug

Spot with Drill Stem, Recondition Hole, Heavy Mud between all plugs

No Circulation problems, Mud Condition 40 vis, 9.4 weight, 10.2 water loss,

EW. 2985, Day 2502, 25^{SK} @ 2520', 100^{SK} @ 1680', 40^{SK} @ 270'

10^{SK} @ 40', 15^{SK} Rat Hole (circulate) Plugging Proposal Received by M. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:00 AM Day: 13th Month: March Year: 19 87

ACTUAL PLUGGING REPORT Ordered 190 5^{SK} 60/40 Pozmix 6% Gel 3% Ca-Cl, 1^{SK} cello

and 8 5/8" Plug, Spotted with Drill Stem, Reconditioned well,

Heavy Mud between all plugs.

1st plug @ 2520 ft w/ 25^{SK} emb, 2ND Plug @ 1680 FT w/ 100 emb (1 cello)

3RD plug @ 270 ft w/ 40^{SK} emb, 5th Plug @ 40' w/ 10^{SK} emb

15^{SK} IN Rat Hole (circulate) Cemented by B.J. Titan

Remarks: 3-23-87 (If additional description is necessary, use BACK of this form) 3-27-1987

INVOICED

(old) (new) observe this plugging.

DATE 3-30-87

Signed M. Schmidt (TECHNICIAN)

INV. NO. 16453