

15-063-21404-00-00

6-21

4-041484

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-21,404

C SW NW /4 SEC. 19, 11 S, 31 W
3400 feet from S section line
4520 feet from E section line

Operator license# 6931

Lease Keller well # 1

Operator: Bowman Oil Company

County Gove

Address: Box 17
Codell, Kansas 67630

Well total depth 4610 feet ^{117.32}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 257 feet
w/190 sx.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00A.M Day: 21 Month: June Year: 93

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company Phone: _____

Were: 4 1/2" casing set @ 4610' w/190 sx. cement. Perf. @ 4289'-4424'.
Anhy. @ 2440'. D.V. @ 2450' w/350 sxs. cement.
Ordered 150 sxs. 60/40 pozmix - 10% gel. plus 200# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 4:00P.M., Day: 21, Month: June, Year: 93

Actual plugging report: Plug bottom with 8 sxs. gel followed with 25
sxs. cement with 100# hulls - balanced at bottom. Pulled tubing to
2450' - spot 50 sxs. cement. Pulled tubing to 1650' - spot 50 sxs. cmt.
Pulled to 850' - spot 25 sxs. cement. Circulate cement - filled casing
and pressured casing to 300#. Plugging complete.

Remarks: Cement to surface in annulus.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES NO

Plugged through TUBING , CASING . Elevation: _____ GL _____

I did did not observe the plugging.

INVOICED

Dennis L. Hamel
RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1993
8-20-1993
CONSERVATION DIVISION
Wichita, Kansas

(agent)

Form CP-2/3

DATE 8-24-93

INV. NO. 38396-1 SEP 15 1993 OCT 06 1993
6-21