

4-071065

9-28

15-063-21458-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-063-21,458

C SW SW /4 SEC. 26, 11 S, 31 W  
660 feet from S section line  
4680 feet from E section line

Operator license# 5011 Lease Schroeder well # 2

Operator: Viking Resources, Inc. County Gove

Address: 105 S. Broadway Well total depth 4616 feet  
Suite #1040 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 229 feet

150.02

Aband. oil well \_\_\_\_, Gas well \_\_\_\_, Input well \_\_\_\_, SWD \_\_\_\_, D & A X

Plugging contractor: Abercrombie Drilling - Allied Cement License# -

Address: 150 N. Main - Wichita, Kansas 67202 - P.O. Box 27 - Oakley, Ks

Company to plug at: Hour: A.M. Day: 28 Month: September Year: 93

Plugging proposal received from: Gary Fisher

Company: Abercrombie Drilling Phone: \_\_\_\_\_

Were: 8 5/8" - 229' S.P. cwc. w/165 sxs. 60/40 pozmix - 2% gel - 3% c.c.  
By: Allied Cement. Elv. 2922' - Anhy. 2430' - Miss. Well - Mud condition  
44 vis. - 9 wt. - water loss 10 - chlorides @ 4215' - 1000 ppm. cl.  
No circulation problems. Proposal 190 sxs. 60/40 pozmix - 6% gel - 1 sx.  
flocele. Spot and displace all cement with drill pipe. Heavy mud  
between all plugs. 25 sxs. @ 2440' - 100 sxs. @ 1620' w/1 sx. flocele.  
40 sxs. @ 279' - 10 sxs. @ 40' - 15 sxs. rathole (circulate)

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 4:30P.M., Day: 28, Month: September, Year: 93

Actual plugging report: Abercrombie ordered 190 sxs. 60/40 pozmix - 6%  
gel - 1 sx. flocele. Spot and displaced all cement through drill pipe.  
Heavy mud between all plugs. (circulated hole)

1st. plug @ 2440' w/25 sxs. cement.

2nd. plug @ 1620' w/100 sxs. cement w/1 sx. flocele.

3rd. plug @ 279' w/40 sxs. cement.

4th. plug @ 40' w/10 sxs. cement.

15 sxs. in rathole (circulate)

Remarks: Cement by Allied Cement. Partial witness by Carl Goodrow.

Condition of casing(in hole): GOOD \_\_\_ BAD \_\_\_ Anhy. plug: YES X NO \_\_\_

Bottom plug(in place): YES \_\_\_, CALC \_\_\_, NO \_\_\_ Dakota plug: YES X, NO \_\_\_

Plugged through TUBING \_\_\_, CASING \_\_\_. Elevation: \_\_\_\_\_ GL

I did [X] did not [ ] observe the plugging.

INVOICED

DATE OCT 12 1993

INV. NO. 38970

110

*Marion J. Schmidt*  
(agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1993  
CONSERVATION DIVISION  
Wichita, Kansas