

6 030775

15-063-21045-00-00

API NUMBER 15-063-21045

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NWNESE SEC. 21, T. 11 S, R. 31  W

TECHNICIAN'S PLUGGING REPORT

2310 feet from S section line

990 feet from E section line

Operator License # 5804

Lease Name WIELAND Well # 1

Operator: DREILING LTD. OFCdo.

County GOVE 15/13

Name & Address 410-17TH ST. STE. 1140

Well Total Depth 4650 feet

DENVER, COLORADO

Conductor Pipe: Size \_\_\_\_\_ feet

80202

Surface Casing: Size 8 5/8 feet 268'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor RED TIGER License Number 530R (79)

Address OTIS, KANSAS

Company to plug at: Hour: AM Day: 4 Month: 7 Year: 19 86

Plugging proposal received from WALT ODEN

(company name) RED TIGER (phone) \_\_\_\_\_

were: 8 5/8 SET @ 268' w/200SX. CIRC. HOLE w/ HEAVY MUD SPOT CEMENT PLUGS w/DRILL PIPE - KEEP HOLE FULL OF HEAVY MUD BETWEEN PLUGS & BARRAGE PLUGS w/MUD. ORDER 190SX. 60/40POR 6%CEL 3%CL B.J. TITAN CMT. CO.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 8:AM Day: 4 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT SPOT D.P. @ 2475 w/25SX. LAYDOWN D.P. TO 1600' DISPLACE 100SX. CMT. MIX. + 1SX. HULLS LAYDOWN D.P. TO 300' DISPLACE 40 SX. CMT. MIX. LAYDOWN D.P. ADJUST MUD LEVEL IN HOLE TO 40' FILL HOLE TO BASE OF CELLAR w/10SX. CMT. MIX. CIRCULATE 15 SX. CMT. MIX. IN RATHOLE TO 110W DEPTH w/JOINT OF PIPE. PLUG COMPLETE

Remarks: EVEN 2957 AWH 2467-97 24 7-30-86  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE AUG - 6 1986

INV. NO. 14610

8-4-1986  
AUG 4 1986

Signed Carl Goodrow (TECHNICIAN)