

4- 062667

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-063-21,440-00-00

SE SE SE /4 SEC. 16 , 11 S , 31 W
330 feet from S section line
330 feet from E section line

Operator license# 4767

Lease R. Garrett well # 1

Operator: Ritchie Exploration, Inc.

County Gove 151.93

Address: 125 N. Market
Suite 1000
Wichita, Kansas 67202

Well total depth 4675 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 237 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: White & Ellis Drilling Company License# 5420

Address: _____

Company to plug at: Hour: 1:00P.M. Day: 7 Month: August Year: 92

Plugging proposal received from: Gilbert G. Scheck

Company: Ritchie Exploration, Inc. Phone: 316-267-5375

Were: Order 215 sks. 60/40 pozmix - 6% gel. - 3% cal. cl. - 1 sk. flocele and 8 5/8" plug. Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:00A.M., Day: 8, Month: August, Year: 92

Actual plugging report: _____

- 1st. plug @ 2500' w/25 sks.
- 2nd. plug @ 1700' w/100 sks.
- 3rd. plug @ 1000' w/40 sks.
- 4th. plug @ 600' w/25 sks.
- 5th. plug @ 40' w/10 sks.
- 15 sks. in Rathole.

Remarks: Allied Cementing Company

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO

Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: GL

I did[] / did not[X] observe the plugging.

DATE 9-14-92

36136

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1992
18-12-1992
CONSERVATION DIVISION
Wichita, Kansas

Gilbert G. Scheck
(agent)