

6010192

15-063-20792-00-00

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-063-20792  
NE, SEC. 19, T. 11 S, R. 31 W  
\_\_\_\_\_ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ feet from W/E section line

Operator License # 5046

Lease Name Jones Well # 2-A

Operator: Raymond oil co Inc.  
Name & Address: 1 Main Place  
Suite 900  
Wichita Ks.

County Grove  
Well Total Depth 4610 149.83 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well (D&A)

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling Co. License Number 5422

Address 801 Union center Wichita Ks.

Company to plug at: Hour: 11 AM Day: 27 Month: 8 Year: 19 84

Plugging proposal received from Wally Towns

(company name) Abercrombie Drilling Co. (phone) 376 262-1841

were: order 195 sk. cement 50/50 permix 6% gel. 3% c.c.

15x hulls 1. 8 5/8 plug 1. 5x flow seal

Heavy mud between all plugs

Pump cement down drill pipe.

Elev. 2997 Anhydrite 2507-33 Arbuckle. No.

Dakota 1600 Plugging Proposal Received by Wally Balthazor  
1397 = 1700 (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part (None)

Operations Completed: Hour: 3:30 PM Day: 27 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 2520 for 20 mi.

25 sk. @ 2520

100 sk @ 1700 mixed with 15x flow seal.

40 sk @ 220 Dumped 15x hulls pushed plug to 40'

10 sk @ 40

10 sk Rat Hole

10 sk mouse Hole

Remarks: Commenting to SUN.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(did / did not) observe this plugging.

DATE 9-12-84  
REV. NO. 3639  
8-27

SEP 04 1984  
9-4-1984  
Signed Wally Balthazor  
(TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas

SH  
Aug 31  
6