

8 7-21 15-063-20360-00-00

6 031273

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-20,360
NE NW, SEC. 19, T 11 S, R 31 W/Ex
4920 feet from S section line

AWS
KC

3800 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552
Operator: Gore Oil Company
Name & Address: 125 N. Market Suite 1750
Wichita, Ks. 67202

Lease Name Pioneer, Well # 1
County Gove 150.22
Well Total Depth 4622 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 316

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Phlling License Number 6050
Address Chase, Ks.

Company to plug at: Hour: AM Day: 21 Month: July Year: 19 89

Plugging proposal received from Bill
(company name) Kelso (phone) _____

were: 8 5/8 " set at 316' w/200 sks. 4 1/2" set at 4619' w/250 sks. Perf
4004'-4340'. PBD 4582'. Order sand and common cement. Pull pipe. Order
250 sks 65/35 10% gle 500# hulls. Halliburton Cement Co. Walker Water Trucks.

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1989
8-10-1989

Plugging Proposal Received by DIVISION Carl Goodrow
Wichita, Kansas (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:20AM Day: 21 Month: July Year: 19 89

ACTUAL PLUGGING REPORT Sand bottom to 3950' w/4 sks common cement on sand w/bailer.
Five shots reovered 1330' of 4 1/2" casing (2500, 1800, 1600, 1330) Squeezed 8 5/8"
w/250 cement blend w/500# hulls mixed into max psi 400#. Close in psi 300#. Plug
complete.

Remarks: (If additional description is necessary, use BACK of this form.)

I (operator) did not observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

INVOICED
DATE 8-15-89
INV. NO. 25605