

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-00119-00-01
Spot: SESW Sec/Twnshp/Rge: 21-11S-31W
712 feet from S Section Line, 3343 feet from E Section Line
Lease/Unit Name: WIELAND OWWO Well Number: 24-21
County: GOVE Total Vertical Depth: 4651 feet

Operator License No.: 9152
Op Name: MAREXCO, INC.
Address: 1225 W. MAIN STE. 107
NORMAN, OK 73069

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 246 220 SX CMT
Production: Size 4.5 feet: 4650 200 SX CMT
Liner: Size feet: 151.16

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/04/2001 8:15 AM
Plug Co. License No.: 9152 Plug Co. Name: MAREXCO, INC.
Proposal Rcvd. from: STEPHEN MARDEN Company: MAREXCO, INC. Phone: (405) 321-3238

Proposed Plugging Method: According to KCC Rules and Regulations.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 12/04/2001 9:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 246' w/220 sxs cmt. 4 1/2" casing at 4650' w/200 sxs cmt.
Port collar at 2612' w/515 sxs cement.
Tied to 4 1/2" casing - pumped 40 sxs cement with 200# hulls,
followed with 11 sxs gel and 115 sxs cement with 200# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.
Tied to 4 1/2" x 8 5/8" annulus and pumped 50 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Total of 205 sxs 60/40 pozmix with 10% gel - 11 sxs gel - 400# hulls.

Remarks: LEASE ALSO KNOWN AS MERRIAM #1. ALLIED CEMENTING COMPANY. HOXIE TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger D. Moses

(TECHNICIAN)

RECEIVED

12-14-2001
DEC 14 2001

KCC WICHITA

INVOICED

DATE 12-19-01

INV. NO. 2002061070

Form CP-2/3

DEC 12 2001

MAREXCO #24-21 21-11-31W
 10403 W. COLFAX AVE., #680 WIELAND 'OWWO' 712' FSL &
 LAKEWOOD, CO 80215 1937' FWL, SW/4
 CONTR R & C DRILLING CTY GOVE

GEOL _____ FIELD PENNY SF
 ELV 2933 KB SPD 12/15/85 CARD ISSUED 2/20/86 IP P 55 60 & 6 BWPD
 2930 GL DRLG COMP 12/16/85 MARM(FT SC) 4411-4414
 A.P. 15-063-01, 885 00119-00-01

| | | |
|---|---|---|
| + | + | + |
| + | + | + |

| LOG | Tops | Depth/Datum |
|-------------|-------|-------------|
| *ANH | 2030+ | 903 |
| HEEB | 3926- | 993 |
| TOP | 3954- | 1021 |
| LANS | 3970- | 1037 |
| BKC | 4246- | 1313 |
| MARM | 4274- | 1341 |
| PAW | 4363- | 1430 |
| FT SC | 4431- | 1498 |
| CHER SD | 4516- | 1583 |
| CONG | 4536- | 1603 |
| ERO MISS | 4541- | 1608 |
| MISS | 4546- | 1613 |
| MISS DOL | 4618- | 1685 |
| LTD | 4551- | 1718 |
| *SAMPLE TOP | | |

OLD INFO: OPERATOR WAS FRED B. & PHILIP ANSCHUTZ, #1 MERRIAM, SPD 9/24/64, SET 8 5/8 " 246 / 220 SX, COMP AS O & A / MISS (CARD ISSUED 10/8/64), CONTR: TERREL DRILLING & PRODUCTION
 DST (1) 4025-4072 (LANS) / OP 60", REC 5' OIL, 520' VSOCM, SIP 1335-1306#, FP 59-259#
 DST (2) 4511-4525 (CHER) / OP 30", WB, REC 20' M, W/OIL SPTS, SIP 1173-991#, FP 32-32#
 NEW INFO: FR 12/3/85, RE-ENTERED 12/15/85, WSH DWN TO 4650', SET 4 1/2 " AT 4642 / 200SX, MICT - CO, PF (FT SC) 4411-4414, W / 2 SPF, AC 250 GAL (15% MCA), SWB DWN, SO, SET 2 7/8 " TBG AT 4449', POP, P 55 60 & 6 BWPD, 1/9/86

NOTE: CORRECTION: 12/3/85 - ORIGINALLY FIRST REPORTED AS C SE SW, WAS #1 MEERIAM