

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE**

Form ACO-1
September 1999
Form Must Be Typed

ORIGINAL

Operator: License # 33344
Name: Quest Cherokee, LLC
Address: 211 W. 14th Street
City/State/Zip: Chanute, KS 66720
Purchaser: Bluestem Pipeline, LLC
Operator Contact Person: Jennifer R. Ammann
Phone: (620) 431-9500
Contractor: Name: TXD Services LP
License: 33837
Wellsite Geologist: Ken Recoy

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

12/15/06	12/18/06	12/19/06
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 133-26746-00-00
County: Neosho

_____ ne _____ ne Sec. 27 Twp. 30 S. R. 19 East West
660 feet from S (N) (circle one) Line of Section
660 feet from (E) / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) (NE) SE NW SW

Lease Name: Diediker Living Trust Well #: 27-1
Field Name: Cherokee Basin CBM

Producing Formation: Multiple

Elevation: Ground: 922 Kelly Bushing: n/a

Total Depth: 943 Plug Back Total Depth: 938.27

Amount of Surface Pipe Set and Cemented at 22' Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from 938.27
feet depth to surface w/ 135 sx cmt.

Drilling Fluid Management Plan AHII NH 7-8-08
(Data must be collected from the Reserve Pit)

Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____

Location of fluid disposal if hauled offsite: **RECEIVED**
KANSAS CORPORATION COMMISSION

Operator Name: _____ License APR 24 2007

Lease Name: _____ Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: **CONSERVATION DIVISION**
WICHITA, KS

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Jennifer R. Ammann
Title: New Well Development Coordinator Date: 4/23/07

Subscribed and sworn to before me this 23rd day of April,
2007.

Notary Public: Serra Klauman

Date Commission Expires: 8-4-2010

KCC Office Use ONLY

Letter of Confidentiality Received
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

TERRA KLAUMAN
Notary Public - State of Kansas
My Appt. Expires 8-4-2010

Operator Name: Quest Cherokee, LLC Lease Name: Diediker Living Trust Well #: 27-1
 Sec. 27 Twp. 30 S. R. 19 East West County: Neosho

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: Compensated Density/Neutron Log Dual Induction Log Gamma Ray Neutron Log	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Name Top Datum See attached
---	--

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4	8-5/8"	20	22	"A"	5	
Production	6-3/4	4-1/2	10.5	938.27	"A"	135	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	823-825/768-770/763-764	300gal 15%HCLw/ 25 bbls 2%kcl water, 576bbls water w/ 2% KCL, Biocide, 7000# 30/70 sand	823-825/768-770 763-764
4	607-609/577-579/557-559/541-543/513-516/485-487	500gal 15%HCLw/ 45 bbls 2%kcl water, 1016bbls water w/ 2% KCL, Biocide, 16000# 30/70 sand	607-609/577-579 557-559/541-543 513-516/485-487
4	396-400/381-385	300gal 15%HCLw/ 36 bbls 2%kcl water, 579bbls water w/ 2% KCL, Biocide, 12000# 30/70 sand	396-400/381-385

TUBING RECORD		Size <u>2-3/8"</u>	Set At <u>862.64</u>	Packer At <u>n/a</u>	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr. <u>1/30/07</u>			Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbls. <u>n/a</u>	Gas Mcf <u>0mcf</u>	Water Bbls. <u>0bbls</u>	Gas-Oil Ratio	Gravity


Disposition of Gas Vented Sold Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____

QUEST

Resource Corporation



211 W. 14TH STREET,
CHANUTE, KS 66720
620-431-9500

TICKET NUMBER 1962

FIELD TICKET REF #

FOREMAN Joe

619300

TREATMENT REPORT & FIELD TICKET CEMENT

DATE	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12-19-06	Diediker Living trust 27-1	27	30	19	NO

FOREMAN / OPERATOR	TIME IN	TIME OUT	LESS LUNCH	TRUCK #	TRAILER #	TRUCK HOURS	EMPLOYEE SIGNATURE
Joe B	6:45	1:30	NO	903127		6.75	Joe B. [Signature]
Tim. A	6:30	1:30	↓	903255		7	Tim [Signature]
Russell A	6:30	1:30	↓	903206		7	[Signature]
Paul H	11:30	1:30	↓	931615		2	Paul [Signature]
TROY W	6:30	1:30	↓	931420		7	Troy [Signature]

JOB TYPE Longstring HOLE SIZE 6 3/4 HOLE DEPTH 943 CASING SIZE & WEIGHT 4 1/2 10.5
 CASING DEPTH 938.29 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 14.5 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 0
 DISPLACEMENT 14.96 DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS:

Installed Cementhead RAN 2 sks gel & 9 bbl dye & 135 sks cement to get eye to surface. Flush pump. Pump Wiper plug to bottom & set first shoe.

938.29	ft 4 1/2" Casing
5	Centralizers
1	4 1/2 float shoe

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION OF SERVICES OR PRODUCT	TOTAL AMOUNT
903427	6.75 hr	Foreman Pickup	
903255	7 hr	Cement Pump Truck	
903206	7 hr	Bulk Truck	
1104	128 SK	Portland Cement	
1124	2	50/50-POZ Blend Cement Baffles 3 1/2" x 4 3/4"	
1126	1	OWC - Blend Cement 4 1/2 wiper plug	
1110	13 SK	Gilsonite	
1107	1.5 SK	Flo-Seal	
1118	2 SK	Premium Gel	
1215A	1 gal	KCL	
1111B	3 SK	Sodium Silicate - Calchloride	
1123	7000 gal	City Water	
		Transport Truck	
931615	2 hr	Transport Trailer 80 VAC	
931420	7 hr	80 Vac	

RECEIVED
KANSAS CORPORATION COMMISSION

APR 24 2007

CONSERVATION DIVISION
WICHITA, KS