

15-063-20142-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
11-2-1972  
NOV 2 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company,  
Complete Address 705 Fourth National Bank Building, Wichita, Kansas.  
Lease Name Wieland Well No. D-1  
Location CSE-SE Sec. 7 Twp. 11 Rge. (E) (W) 31  
County Gove Total Depth 4655'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Above  
Address        License No.         
Operation Completed: Hour 12:45 PM Day 31 Month 10 Year 1972

The above well was plugged as follows:

251'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1425'.

Circulated hole with heavy mud. Pulled DP to 1650' and displaced 110 Cu. Ft. cement  
thru DP from 1650' to 1325'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols  
Well Plugging Supervisor

INDEXED  
DATE 11/2/72  
INV. NO. 6566-u