

KANSAS

W

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
9-25-1972
SEP 25 1972
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company,

Complete Address 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name Hays-Pioneer Feed Yard Well No. A-1

Location CNE-NW Sec. 17 Twp. 11 Rge. (E) (W) 31

County Gove Total Depth 4674'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 4:00 AM Day 22 Month 9 Year 1972

The above well was plugged as follows:

275'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1400'.

Circulated hole with heavy mud. Pulled DP to 1600' and displaced 110 Cu. Ft. cement
thru DP from 1600' to 1275'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 9/28/72
INV. NO. 6360-W