

15-063-20103-00-00

Form CP-3
Rev. 6-4-68

KANSAS

de

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-30-1971
DEC 30 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company,
Complete Address 705 Fourth National Bank Building, Wichita, Kansas.
Lease Name Merrian Well No. A-1
Location CNW-NW Sec. 21 Twp. 11 Rge. (E) (W) 31
County Gove Total Depth 4670'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 10:30 AM Day 24 Month 12 Year 1971

The above well was plugged as follows:

242'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1300'.

Circulated hole with heavy mud. Pulled DP to 1525' and displaced 110 Cu. Ft. cement
thru DP from 1525' to 1200'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Nichols*
Well Plugging Supervisor

DATE 1-11-72
INV. NO. 4943-W