

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Breck
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 - - (OWWO) (of this well)

Operator's Full Name D. J. MARBLEY

Complete Address 211 WEST 36th ST. - HAYS, KANS. 67601

Lease Name POSEGATE Well No. #2

Location NW-NW-NW Sec. 6 Twp. 10^s Rge. 17^W (w) 12

County ROCKS Total Depth PBTD 3532^{ft} 114^{ft} 79

Abandoned Oil Well Gas Well Input Well SWD Well D&A
RTKCC

Other well as hereafter indicated WASH DOWN - WENT OUT OF HOLE - LOST HOLE

Plugging Contractor J. B. COLLINS - dba, T. B. J. OIL CO. T ALLIED CMT.

Address 1007 CODY, HAYS, KANS License No. 716 RECEIVED

Operation Completed: Hour 1:30^{PM} Day 25 Month AUG. Year 1980
STATE CORPORATION COMMISSION

The Above well was plugged as follows:

AUG 29 1980
8-29-80
CONSERVATION DIVISION
Wichita, Kansas

LOST HOLE - WENT OUT OF HOLE AT 2100^{ft} COULDN'T GET BACK
CAVE IN AT APPROX 1100^{ft}.

8 5/8" 178^{ft} SR. CUL -> 4 1/2" SET AT 3590^{ft} - PLUG. BACK TO 3532^{ft}
PERFS - 3570^{ft} TO 3261^{ft} NO PIPE RECOVERY.

ORDERED 140^{ft} 30% PERMIX 6% GEL. T 4^{ft} HULL'S - PUMPED IN WITH PUMP TRUCK.
PUT IN 25^{ft} CMT -> 3^{ft} HULL'S -> 75^{ft} CMT. - MAX PRESSURE 500^{PSI}
PUT 40^{ft} CMT T 1^{ft} HULL'S IN ANNULUS - MAX PRESSURE 250^{PSI}

RETURNED ON AUG. 29th @ 11:45^{PM} AND FILLED 4 1/2" T 8 5/8" WITH 1/2 yd. READY MIX.

I hereby certify that the above well was plugged as herein stated. (CEMENTED BY ALLIED CMT)

INVOICED

DATE 9-4-80

INV. NO. 3009-w

Signed: Marvin Schubert
Well Plugging Supervisor