

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 125-40
LOCATION SW NE NW
SEC. 6 TWP. 10 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease ~~Pogate~~ Posegate

Operator Petroleum Inc Address 311 E 3rd Wichita, Kans

Field _____ County Rooks

Total Depth 3610 Feet.

Plugging Contractor Morgan Pipe Pulling

Plugging Contractor's License No. 43

Address _____
(Describe briefly the manner in which the well was plugged)

8 5/8" at 194' circulated with cement - 5 1/2" at 3609' with
75 sax cement behind - P. B. to 3482', perforated at 3444',
Filled with chat to 3430', set 4 sax cement with dump bailer,
pulled 2100' 5 1/2" - mud to 190', rock and 15 sax cement, mud to
35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 6 TWP 10 R 17W
BOOK PAGE 25 LINE 40

RECEIVED
STATE CORPORATION COMMISSION
9-6-55
SEP - 6 1955
CONSERVATION DIVISION
Wichita, Kansas

E. J. [Signature]
District Conservation Agent
Date 9-2-55