

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED  
STATE CORPORATION COMMISSION  
3-20-67  
MAR 20 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Sterling Drilling Company

Complete Address: Box 127 Sterling Kansas

Lease Name Jones Well No. 1

Location SW SE NE Sec. 9 Twp. 10 Rge. 17 (E) (W) X

County Rooks Total Depth 3550

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: \_\_\_\_\_ Co, Tools \_\_\_\_\_

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 11 P Day 17 Month 3 Year 1967

The Above well was plugged as follows:

RTD 3550 8 5/8 csg set at 155' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 20 sc cem.

thru drill pipe. Heavy mud to 150' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 3/20/67  
INV. NO. 4927-W

Signed: Rio J. Messing  
Well Plugging Supervisor