

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 110-39

LOCATION SW SW SW

SEC. 18 TWP. 10 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Garvert

Operator Champlin Refg Co Address Box 552 Enid, Okla.

Field _____ County Rooks

Total Depth 3755 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 160' Circulated with cement - 5 1/2" at 3754' with
100 sax cement behind - perforations at 3648' - Baker plugs and
cement to 3697' - Filled with sand to 3650', set 4 sax cement with
dump bailer, pulled 2980' 5 1/2" - filled with mud to 100', set rock
and 10 sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

RECEIVED
STATE OF KANSAS
7-8-53
JUL 8 1953
CONSERVATION DIVISION
Wichita, Kansas

Edouard Perry
District Conservation Agent

Date 7-3-53

PLUGGING
FILE SEC 18 T 10 R 17W
BOOK PAGE 110 LINE 39