

15-063-20103-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Gove County, Sec. 21 Twp. 11S Rge. 31 (W)  
Location as "NE/CNW/SW" or footage from lines C NW NW  
Lease Owner Pickrell Drilling Company  
Lease Name Meerian "A" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 24 19 71  
Application for plugging filed December 24 19 71  
Application for plugging approved December 24 19 71  
Plugging commenced December 24 19 71  
Plugging completed December 24 19 71  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4670 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	242'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug @ 1525' w/110 sacks, Middle Plug @ 275' w/30sacks,  
Top Plug @ 40' w/10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION  
1-3-1972  
JAN 3 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. W. Sebitts \_\_\_\_\_ (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 1971

My commission expires January 19, 1973

Esther Lamone  
Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita, Kansas 67202

Rotary Drilling Commenced 12/9/71

Rotary Drilling Completed 12/24/71

LOCATION: Meerian "A" No. 1, C NW NW Sec. 21-11S-31W,  
Gove County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Run 6 Jts. 8-5/8" surface casing set @ 242' KB. Cemented w/140  
Sacks. Completed 7:15 P.M. Circulated.

No oil string run. D & A, Plugged 5:15 A.M. December 24, 1971.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Surface Soil			
60	Sand	<u>C.F.S.</u>		
645	Shale	3998	4165	4560
1715	Shale w/Sand Streaks	4013	4195	4600
1840	Shale	4040	4221	4605
1990	Sand & Shale	4044	4245	4625
2475	Shale	4060	4280	4645
2545	Anhydrite	4085	4305	4670
2660	Shale	4100	4330	
2839	Shale & Lime	4115	4460	
3200	Lime	4145	4540	
3575	Lime & Shale			
3710	Shale & Lime			
3870	Lime & Shale			
4167	Lime			
4221	Lime & Shale			
4670	Lime, Miss., RTD			
			<u>Slope Tests</u>	
			2000	
			2500	
			3000	
			3500	
			4000	
			4500	


RECEIVED  
STATE CORPORATION COMMISSION  
JAN 3 1972  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 29th day of December, 19 71, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.



My commission expires: January 19, 1973

Esther Lamone  
Notary Public