

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Gove SEC. 16 TWP. 11S RGE. 31W E/W
 Location as in quarters or footage from lines:
SE SW

Locate Well
 correctly on above
 Section Platt.

Lease Owner George R. Jones
 Lease Name WEILAND Well No. 1
 Office Address 125 N. Market, Suite #1210, Wichita, KS
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed July 10, 1982
 Application for plugging filed July 10, 1982
 Plugging commenced July 10, 1982
 Plugging completed July 10, 1982

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well _____
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4605'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Formation	Content	From	To	Size	Put In	Casing Record
						Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____
 to _____ feet for each plug set.

Set 1st plug @ 1580' with 80 sx
 Set 2nd plug @ 300' with 40 sx.
 Set 3rd plug @ 40' Sol. Bridge with 10 sx.
 10 sx. in Rathole.
 50-50 posmix, 4% gel, 3% c.c.
 Plug was down @ 7:00 p.m., 7/10/82

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick ss.
Jack K. Wharton, Ass. Sec./Treas. (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Jack K Wharton
 801 Union Center, Wichita, KS 67202
 (Address)

SUBSCRIBED AND SWORN TO before me this _____ day of _____, 19 _____

My Commission expires: 7-13-85

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 16 1982
 Elizabeth G. Terry Notary Public
 CONSERVATION DIVISION
 Wichita, Kansas



JUL 20 1982

15-063-20587-00-00

CONTRACTORS WELL LOG

OPERATOR: George R. Jones
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: WEILAND #1
 LOCATION: SE SW, Sec. 16-11S-31W
 Gove County, Kansas
 SPUD DATE: 7/02/82
 COMPLETION DATE: 7/10/82
 API No. 15-063-20,587

0	132	Surface Shale & Sand
132	822	Shale & Sand
822	2507	Sand & Shale
2507	2535	Anhydrite
2535	2765	Shale
2765	3234	Sand & Shale
3234	3485	Shale & Lime
3485	3910	Lime & Shale
3910	4080	Shale & Lime
4080	4130	Lime & Shale
4130	4450	Shale & Lime
4450	4550	Lime & Shale
4550	4605	Shale & Lime
	4605	Rotary Total Depth

Spud hole @ 2:00 p.m., 7/02/82. Drilled 286' of a 12½" hole. Ran 7 jts. of 8 5/8" 20# casing (tally 276.38') set @ 283.38'. Cemented with 200 sx. Common, 2% gel, 3% c.c. Cement did circulate. Plug was down @ 7:00 p.m., 7/02/82.

4605' RTD. Set 1st plug @ 1580' with 80 sx. Set 2nd plug @ 300' with 40 sx. Set 3rd plug @ 40' Sol. Bridge with 10 sx. 10 sx. in Rathole. 50-50 posmix 4% gel, 3% c.c. State plugger Carl Goodrow. Job complete @ 7:00 p.m., 7/10/82.

SAMPLE TOPS:

Anhydrite 2507'
 B/Anhydrite 2535'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack K. Wharton, Assistant Sec./Treas. of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct of the log of the WEILAND #1, SE SW, Sec. 16-11S-31W, Gove County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: *Jack K. Wharton*
 Jack K. Wharton, Ass. Sec/Trea

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 21st day of July, 1982.

my commission expires: 7-13-85

RECEIVED
 STATE CORPORATION COMMISSION
 7-27-1982
 JUL 27 1982
 CONSERVATION DIVISION
 Wichita, Kansas

Elizabeth G. Terry
 Elizabeth G. Terry
 Notary Public

