


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rocks _____ County. Sec. 6 Twp. 10 Rge. 17 W (W)
Location as "NE/CNW/SW" or footage from lines SW-NE-NW
Lease Owner Petroleum, Incorporated
Lease Name Posegate Well No. 11
Office Address 311 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed October 24 1951
Application for plugging filed June 10 1955
Application for plugging approved August 30 1955
Plugging commenced August 31 1955
Plugging completed September 2 1955
Reason for abandonment of well or producing formation _____
Depletion of Produccible Zones
If a producing well is abandoned, date of last production May 28 1955
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Kansas City Depth to top 3286' Bottom 3513' Total Depth of Well 3610 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	oil & water	3490'	3496'	8-5/8"	194'	None
Kansas City	oil & water	3460'	3466'	5-1/2"	3,609'	1,997'
Kansas City	oil & water	3444'	3450'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

(Baker Plug at 3,482')

Filled hole from 3482' to 3440' with crushed rock and placed 4 sacks cement at 3440'. Mudded up with heavy mud to 190' and made a solid rock bridge. Filled hole with 15 sacks cement 190' to 145'. Mudded up with heavy mud from 145' to 35' and made a solid rock bridge. Filled hole to base of well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service (License #43)
Address 102 West 18th Street, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
C. J. Wiltse (employee of owner) or ~~#####~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. J. Wiltse
Rural Route 2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 55

My commission expires November 21, 1957 Joy E. Anderson Notary Public.

24-7368-5 3-53-20M

PLUGGING
FILE SEC 6 T 10 R 17W
BOOK PAGE 125 LINE 40

RECEIVED
STATE CORPORATION COMMISSION
9-17-55
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG POSEGATE #1

Petroleum, Inc., Lease Owner

Section 6, Twp. 10S, Rge. 17W

Garvey Oil, Contractor

Location: SW NE NW

Drilling Commenced: October 9, 1951
Drilling Completed: October 29, 1951

County: Rocks

Casing Record: 194' of 8 5/8" w/150 sax
3609' of 5 1/2" w/75 sax

Elevation: 2110 R.B.

Rotary Total Depth: 3610'

All figures indicate bottom of formation:

95	Sand & Shale
550	Shale & Shells
620	Sand & Red Bed
910	Shale & Shells
1070	Sand
1150	Shale
1404	Shale, Shells & Red Bed
1440	Anhydrite
1645	Red Rock, Shale & Shells
2000	Shale, Shells & Lime & Shells
2125	Shale
2700	Lime & Shale
3020	Shale
3535	Lime
3599	Lime & Chert
3610	Lime
3610'	R.T.D.

Tops:

3245 (-1135)	Heebner
3288 (-1178)	Lansing
3589 (-1479)	Arbuckle

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1951
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By *Eric H. Jager*
Eric H. Jager

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 29th day of October, 1951.

PLUGGING

FILE SEC 6 T 10 R 17W
BOOK PAGE 123 LINE 40

Charlotte Hudson
Notary Public

My commission expires: October 13, 1954