

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-30199-0001

API NUMBER 15-E-12,384

LEASE NAME Collins "E"

WELL NUMBER 4

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 6 TWP. 10S RGE. 17 (X) or (W)

COUNTY Rooks

Date Well Completed 10/2/66

Plugging Commenced 3/9/90

Plugging Completed 3/9/90

Yes

LEASE OPERATOR Davis Bros. Oil Producers, Inc. Tulsa, OK

ADDRESS One Williams Center, Suite 2000 74172

PHONE (918) 584-3581 OPERATORS LICENSE NO. 5560

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? NO If not, is well log attached? Log attached to CP-1 filed 2/19/90

Producing Formation Lansing/Kansas Depth to Top 3418 Bottom 3511 T.D. 3562  
City

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/Kansas City	Oil	3418	3511	8 5/8	151	0
				4 1/2	3560	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped in 50 sx common w/ 1/4# flocele plus pumped in 4 1/2" casing 225 sx cement w/ 1/4# flocele plus 3 sx hulls mixed in cement. Max 500#. ST 200#. Pumped in 8 5/8" casing 75 sx cement with 1/4# flocele plus 2 sx hulls mixed in cement. Max 300#. ST 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton

License No. 5287

Address East 8 Street, Hwy 40, Hays, KS 67601

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Douglas R. Lewis

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Douglas R. Lewis

One Williams Center, Suite 2000

(Address) Tulsa, OK 74172

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 90

5-7-90  
1990

Melody M. Sullivan  
Notary Public

My Commission Expires: Aug. 6, 1993

CHASER AND SONS  
NOTARY PUBLIC