

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-00992-0001

API NUMBER N.A.  
LEASE NAME Ross C-1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER C-1  
2970  
330 Ft. from S Section Line  
4290  
4250 Ft. from E Section Line

LEASE OPERATOR Carmen Schmitt Inc.  
ADDRESS Box 47 Great Bend KS, 67530  
PHONE# (316) 793-5100 OPERATORS LICENSE NO. 6569  
Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SEC. 7 TWP. 10 RGE. 17 (E) or (W)  
COUNTY ROOKS  
Date Well Completed 10-1-59  
Plugging Commenced 8-27-96  
Plugging Completed 8-27-96

The plugging proposal was approved on 8-27-96 (date)  
by Dennis Homel (KCC District Agent's Name).

Is ACO-1 filed? NA If not, Is well log attached? \_\_\_\_\_

Producing Formation Lasing KC. Depth to Top 3306 Bottom 3679 T.D. 3679

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled	RECEIVED STATE CORPORATION COMMISSION 9-6-96 SEP 6 1996
		<u>0</u>	<u>155</u>	<u>8 5/8</u>	<u>155</u>	<u>0</u>	
		<u>0</u>	<u>3670</u>	<u>5 1/2</u>	<u>3670</u>	<u>0</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Well squeezed Dakota leak with 325 sk from 925 to surface in 1961  
PERFORATED AT 1440' & 1925'. Ran tag to 3000' & pumped 110 sks cement w/ 300\* bulls. Pulled tag to 1850' and circulated cement to surface with 168 sks. Pulled tag. Tied on to production csg. & pumped 50 sks cement. Max 600\* SIP 300\*.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. Inc. License No. \_\_\_\_\_  
Address \_\_\_\_\_

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carmen Schmitt Inc.  
STATE OF Kansas COUNTY OF Barton, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Curtis J. Hirschman

(Address) Box 47 Great Bend Kansas 67530

before me this 30<sup>th</sup> day of August, 19 96

Elaine Schick  
Notary Public

KCC

SEP 4 1996



HAYS, KS

My Commission Expires: 12-13-1999

8-27-96 LK Wire Line perforated 1440' and 1925'. Randy's Well Service  
ran tubing to 3000' Allied Cementing mixed 300 lbs balls and  
110 sk 60-40-10% gel pump-d down tubing. Pulled tubing to 1850'  
mixed 165 sks pump-d down tubing. Pulled tubing out of hole.  
mixed 50 sks squeezed at 600 psi. Shot in pressure was 300 psi

300  
A  
ELECTRIC  
CHECK  
1996