

15-163-19398-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby  
Wichita, Kansas

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-8-18-64

LEASE NAME Kleinschmidt "B"

RECEIVED  
STATE CORPORATION COMMISSION  
9-16-88  
SEP 16 1988  
CONSERVATION DIVISION  
Wichita, Kansas

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days. *RT KCC*

WELL NUMBER 1  
2970

1,650 Ft. from S Section Line

1650  
990 Ft. from E Section Line

LEASE OPERATOR Davis Bros. Oil Producers, inc.

SEC. 7 TWP. 10S RGE. 17 (X) or (W)

ADDRESS One Williams Center, Suite 2000 Tulsa, OK  
74172

COUNTY Rooks

PHONE# (918) 584-3581 OPERATORS LICENSE NO. 5560

Date Well Completed 7-9-64

Character of Well Oil

Plugging Commenced 7-29-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-29-88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? No, Filed w/ CP-1 6-28-88

Producing Formation Lansing/KC Depth to Top 3434 Bottom 3494 T.D. 3684

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Lansing/KC</u>	<u>Oil</u>	<u>3434</u>	<u>3494</u>	<u>8 5/8"</u>	<u>160</u>	<u>0</u>
				<u>4 1/2"</u>	<u>3682</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Pumped in 4 1/2" casing 150 sx cmt w/ 1/4# Flocele, 3 sx hulls mixed in cmt. Max 800#. SI 800#. Pumped in 8 5/8" casing 100 sx. cmt w/ 1/4# Flocele plus 3 sx hulls mixed in cmt. Max 400#. SI 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. Titan License No. \_\_\_\_\_

Address Hays, Kansas

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Douglas R. Lewis (Employee of Operator) or (~~XXXXXX~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Douglas R Lewis  
One Williams Center, Suite 2000  
(Address) Tulsa, OK 74172

SUBSCRIBED AND SWORN TO before me this 14th day of September, 19 88

Melody M. Sullivan  
Notary Public

My Commission Expires: Aug. 6, 1989