

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

9-20-77

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Arnold of Davis Oil Prod. has this date requested permission to plug the following described well:

Mr. Arnold guarantees payment of the plugging fee.

Operator's full Name: Davis Bros. Oil Producers, Inc.

Complete Address: 500 Mc Farlin Bldg., Tulsa. Okla.

Lease Name: White "A" Well No. 3

Location: SE NE NE Sec. 8 Twp. 10 Rge. (E)(W) 17

County: Rooks Total Depth 3550' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Arnold was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 550' thru drill pipe. Heavy mud to 160' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent