

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS, 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Rice of Sterling Drilling has this date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Sterling Drilling Company

Complete Address: Box 127 Sterling, Kansas

Lease Name: Jones Well No. 1

Location: SW SE NE Sec. 9 Twp. 10 Rge. 17 (E)(W) X

County Rooks Total Depth 3550 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rice was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace
20 sc cement thru drill pipe. Heavy mud to 150' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Russ F. Wassery
Conservation Division Agent