

9-6

103
R

6-062496

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-01849-0000

SE /4 SEC. 31, 10 S, 17 W
990 feet from S section line
2310 feet from E section line

Operator license# 4933 Lease Hahn well # 4

Operator: Vac Petroleum Co. Inc. County Rooks

118.10

Address: Box 780106 Well total depth 3634 feet
Wichita, Kansas 67278 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Great Bend Casing Pullers, Inc. License# 4635

Address: Box 768, Great Bend, Kansas 67530

Company to plug at: Hour: 8:00A.M. Day: 6 Month: September Year: 91

Plugging proposal received from: Gary Burke

Company: Great Bend Casing Pullers, Inc. phone: 316-793-9711

Were: Order 250 sks. 60/40 posmix - 8% gel. - 5 sks. hulls.

Well had been D.V. from 1460' to surface.

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All], Part], None]

Completed: Hour: 12:30P.M. Day: 6 Month: September Year: 91

Actual plugging report: 8 5/8" set at 160' w/115 sks. 5 1/2" set at 3632' w/250 sks. Top perf. at 3334'. Plugged bottom with sand and 5 sks. cement to 3275'. Shot pipe 4 times and recovered 189'. Pumped in 8 5/8" casing, 25 sks. cement, followed with 5 sks. hulls in 125 sks. cement w/500 P.S.I.

Remarks: By: Allied. Ran line to 3000'.

I did observe the plugging.

Gilbert G. Scheck E.A.S.

INVOICED

DATE 10-16-91

INV. NO. 33379

Rec'd
Jun 21, 1991
KCC

(agent)
Form CP-2/3