

15-109-20453-00-00

1-27-88

113

6020448

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 109-20,453  
N/2 N/2 NW SEC. 35, T 11 S, R 33

4840 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8541

Lease Name Bertrand Well # 2 Z

Operator: Petex Inc.  
Name & Address: Rt. 2 Box 553  
Rogerville, Mo. 65742  
417-887-6289

County Logan 151.94  
Well Total Depth 4675 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor R. and C. Drilling License Number 9087

Address Hays, Ks.

Company to plug at: Hour: AM Day: 27 Month: Dec Year: 19 87

Plugging proposal received from John Wise

(company name) R and C Drilling (phone) 913-625-4548

were: Order 190 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.  
Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Gil Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 4:45PM Day: 27 Month: Jan Year: 19 88

ACTUAL PLUGGING REPORT Cir heavy mud.

- 1st plug at 2610' w/25 sks
- 2nd plug at 1600' w/100 sks 1 sk F.C.
- 3rd plug at 220' w/40 sks
- 4th plug at 40' w/10 sks w/wiper
- 15 sks in rat hole.

Remarks: Allied Cement Co.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-29-88 2-23-1988  
INV. NO. 19940

Signed Gilbert Balthazor (TECHNICIAN)