

8-31 15-109-20461-00-00

To: 6 100359
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 109-20,461

C E/2 NE, SEC. 32, T 11 S, R 33 W/E
3960 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8541

Lease Name Keller Well # 1

Operator: Petex Inc.
Name & Address: 1111 S. Glenstone #1-104
Springfield, Mo.
65804

County Logan 152.75
Well Total Depth 4700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling License Number 5104

Address Great Bend, Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling (phone) _____

were: Spot through drill pipe w/heavy mud between all plugs

1st plug at 2600' w/25 sks

2nd plug at 1610' w/100 sks

3rd plug at 260' w/40 sks

4th plug at 40' w/wiper plug and 10 sks Water well 10 sks

Rathole 15 sks 2.1 1988 Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operation completed by Agent?: All _____ Part _____ None

Operations Completed: Hour 10:00AM Day 31 Month August Year 19 88


ACTUAL PLUGGING REPORT Hole reported plugged as above.

Order 190 sks 60/40 Poz w/6% Gel and 2 sks Celloflake.

Elevation 3112', Anhydrite depth: 2590' - 2610'

Remarks: Did not penetrate Arbuckle Cemented by Allied.
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed  (TECHNICIAN)

David K. Wann FORM CP-2/3 Rev. 01-84

INVOICED
DATE 10-25-88
INV. NO. 27710

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1988
10-21-1988
CONSERVATION DIVISION
Wichita, Kansas