

4-071169

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

3-11

API Number: 15-109-20,612

W2 NW SE /4 SEC. 30, 11 S, 33 W
1980 feet from S section line
2310 feet from E section line

Operator license# 9860

Lease: Shelby Well # 1

Operator: Castle Resources, Inc.

County: Logan

Address: 1200 East 27th - Suite #C
Hays, Kansas 67601
Jerry Green

Well total depth 4800 156.00 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 210 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling, Inc. License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 11 Month: March Year: 1996

Plugging proposal received from: Tom Alm

Company: Discovery Drilling, Inc. Phone: 913-625-5155

Were: 8 5/8" - 210' S.P. cwc. w/140 sxs 60/40 pozmix - 2% gel - 3% c.c. By Allied Cement.
Elv. 3108' - Anhy. 2571' - Miss. Well. No circulation problems. Mud condition 54 vis. -
9.4 wt. - 10.2 water loss - 2000 ppm cl at 4775'. Proposal 200 sxs 60/40 pozmix - 6% gel and
1/4# flocele per sack - spot and displace all cement through drill pipe - heavy mud between
all plugs. 25 sxs at 2580' - 100 sxs at 1600' - 40 sxs at 250' - 10 sxs 40' - 15 sxs in
rathole (circulate) - 10 sxs in mousehole (circulate).

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 9:15 P.M. Day: 11 Month: March Year: 1996

Actual plugging report: Castle Oil ordered 200 sxs 60/40 pozmix - 6% gel and 1/4# flocele per sack. Spotted and displaced all cement through drill pipe with heavy mud between all plugs.

- 1st. Plug at 2580' w/25 sxs. cement.
- 2nd. Plug at 1600' w/100 sxs. cement.
- 3rd. Plug at 250' w/40 sxs. cement.
- 4th. Plug at 40' w/10 sxs. cement.
- 15 sxs in rathole (circulated). 10 sxs in mousehole (circulated).

Remarks: Cemented by Allied Cement.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: GL

I did [] / did not [X] observe the plugging.

Marion J. Schmidt
(agent)
Form CP-2/3

RECEIVED
KANSAS CORP COM
MAR 13 11:17
3-15-1996

INVOICED

DATE MAR 26 1996

INV. NO. 45124

3-11 MAY 17 1996